

DATE: November 20, 2012

TEST NO: 2

COMPANY DETAILS:

Company Name: Bank Islami
 Contact Person: Mr. Salman-ur-Rehman
 Designation: Operations Manager
 Address: 8C-A & 9D-A, Commercial Area Phase II, DHA, Karachi
 Contact Details: (021)- 111-BIP-111 (111-247-111)

INSTALLATION DETAILS:

Make: Dawlance
 Type: Wall Mount Split
 Capacity: 02 Ton
 Line Voltage: 220 V, Single Phase
 Location: Customer Waiting Area

TEST RESULTS

Without AircoSaver

	Date	Time	Temp	Units
Start	19-Nov	12:58	22°C	11.35
Stop	19-Nov	15:51	22°C	16.40
Total		2:53		5.05

Units Consumed per Hour: 1.7514

With AircoSaver

	Date	Time	Temp	Units
Start	20-Nov	14:07	22°C	21.32
Stop	20-Nov	17:00	22°C	25.21
Total		2:53		3.89

Units Consumed per Hour: 1.3491

SAVINGS in KWH: 0.4022

SAVINGS in %: 22.96%

CLIENT ACKNOWLEDGEMENT
 SALMAN-UR-REHMAN
 Customer Manager
 Bank Islami
 DHA Phase II, (111-247-111), Karachi

FOR ENERTECH